MWSS at Kottayam

SI.No	Item Name	Rate	Unit	Qty	Total
1	Earth work in rough excavation, banking	1081.86	cum	36.00	38946.90
	excavated earth in layers not exceeding 20				
	cm in depth, breaking clods, watering,				
	rolling each layer with 1/2 tonne roller or				
	wooden or steel rammers, and rolling every				
	3rd and top-most layer with power roller of				
	minimum 8 tonnes and dressing up in				
	embankments for roads, flood banks,				
	marginal banks and guide banks or filling				
	up ground depressions, lead up to 50 m				
	and lift up to 1.5 m: All kinds of soil (Code:				
	2.2.1)				
Platform Constructions					
2	KSEB		-	- (KSEB	14000.00
				Charges)	
3	Deduct for not watering the excavated earth for banking (Code: 2.5)	47.91	cum	600.00	28748.44
				(Estimated	
				Value)	
Subtotal					81695.34
GST (18%)					14705.16
Unforeseen (5%)					4084.77
Grand Total Rounded To Next 1000					101000.00

District Officer
(Seal & Signature)