

sdasdddddddddddddddd ddddddddddddddd
sdasdddddddddddddddd ddddddddddddddd
sdasdddddddddddddddd ddddddddddddddd

dsadadad
adadadad
adasddad

Sl.No	Item Name	Qty	Unit	Rate	Total
1	Flushing (Developing) Borewell (Code: GWDDR105)	1.0000	each	5790.00	5790.00
Pump & Accessories					
2	Compressor pump 2 HP single phase (Code: GWDMR065)	1.0000	each	27540.00	27540.00
3	Compressor pump fitting charge (Code: GWDDR055)	1.0000	each	3615.75	3615.75
4	Providing and fixing G.I. pipes complete with G.I fittings including trenching and refilling etc. External work 25 mm dia nominal bore (18.12.3) (Code: GWDDR243)	15.0000	meter	362.84	5442.60
5	20 mm dia HDPE pipe (DG) (8kg) (Code: GWDMR076)	50.0000	meter	15.00	750.00
6	32 mm dia UPVC pipe (Code: GWDMR072)	60.0000	meter	270.00	16200.00
7	Providing and fixing G.I. Union in G.I pipe including cutting and threading the pipe and making long screws etc. complete (New work): 32 mm nominal bore (18.46.4) (Code: GWDDR271)	1.0000	each	355.48	355.48
8	14 mm thick nylon rope (Code: GWDMR069)	65.0000	meter	49.20	3198.00

Sl.No	Item Name	Qty	Unit	Rate	Total
9	Supply and drawing FRLS PVC insulated & sheathed 650/1100 V grade 3 core copper conductor flat cable for submersible pump motor conforming to IS 694 part I 1990 as required including giving necessary connections of the following sizes. 4 sq mm (90.6.6.3) (Code: GWDDR117)	20.0000	meter	132.45	2649.00
10	GI Bend 40 mm (Code: GWDMR053)	1.0000	each	162.00	162.00
11	GI Socket 40 mm (Code: GWDMR057)	1.0000	each	69.69	69.69
12	Providing and fixing gun metal non-return valve of approved quality (screwed end): 40 mm nominal bore Horizontal (18.19.3.1) (Code: GWDDR260)	1.0000	each	707.55	707.55
13	40 mm SS Adapter (Code: GWDMR080)	1.0000	each	960.00	960.00
Electrification					
14	Installation of Single Phase Panel board where new electricity connection is required (Excluding Motor Starter) (Code: GWDDR363)	1.0000	each	12394.15	12394.15
15	S & F Motor starters of the following ratings Submersible pump controllers with ammeter,DPMCB for single phase 2 HP submersible motor pumps (DOL) (90.14.28.13) (Code: GWDDR134)	1.0000	each	1953.71	1953.71
Civil Structures					
16	Well Protection Cover (Code: GWDDR001)	1.0000	each	3800.00	3800.00
17	Metallic Pump House of size 1.2 x 0.9 x 2 m (Code: GWDDR006)	1.0000	each	26000.00	26000.00
18	Angle Iron Structure To Support 3000 Litres Capacity Water Tank At 4 m Height (Code: GWDDR003)	1.0000	each	62000.00	62000.00
Water Tank & Fittings					
19	Providing and placing on terrace (at all floor levels) polyethylene water storage tank :ISI 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. (Code: 18.48)	3000.0000	Litre	8.41	25230.00

Sl.No	Item Name	Qty	Unit	Rate	Total
20	PVC Tank connector 40 mm (Code: GWDMR035)	1.0000	each	240.00	240.00
21	PVC Tank connector 50 mm (Code: GWDMR036)	1.0000	each	288.00	288.00
22	PVC Ball valve 40 mm (Code: GWDMR042)	1.0000	each	336.00	336.00
23	PVC Ball valve 50 mm (Code: GWDMR043)	1.0000	each	456.00	456.00
Pumping & Distribution Network					
24	Providing and fixing PVC pipes including jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 50 mm dia 10Kgf/cm ² (50.18.9.6.1) (Code: GWDDR192)	100.0000	meter	258.40	25840.00
25	Providing and fixing PVC pipes including jointing of pipes with one step PVC solvent cement, trenching refilling & testing of joints complete as per direction of Engineer in Charge 40 mm dia 10Kgf/cm ² (50.18.9.5.1) (Code: GWDDR190)	100.0000	meter	250.38	25038.00
26	Providing and fixing PVC pipes including jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 32 mm dia 10.Kgf/cm ² (50.18.9.4.1) (Code: GWDDR188)	100.0000	meter	215.37	21537.00
27	Providing and fixing PVC pipes includes jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 25 mm dia 10KGF/cm ² (50.18.9.3.2) (Code: GWDDR187)	100.0000	meter	192.66	19266.00
28	Hydrants with tap (for individual families of size 0.6 X 0.3 M platform) (Code: GWDDR062)	10.0000	each	1702.31	17023.10
Supplementary Works					

Sl.No	Item Name	Qty	Unit	Rate	Total
29	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil. and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m: All kinds of soil Pipes, cables etc, not exceeding 80 mm dia (Code: 2.10.1.1)	250.0000	metre	221.83	55457.50
30	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) (Code: 15.2.1)	6.0000	cum	1742.42	10454.52
31	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4)1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) (Code: 4.1.4)	6.0000	cum	6273.90	37643.40
32	KSEB Charges	2.0	each	1000.00	2000.00
Subtotal					414397.00
GST (18%)					74592.00
Unforeseen					12311.00
Grand Total Rounded to Next 100					501300.00
Amount in Words: Five Lakh, One Thousand, Three Hundred Rupees Only					
<i>All Items should be as per ISI Standards</i>					
sdasdddddddddddddd dddddddddddddd					

Assistant Engineer
(Seal & Signature)

Assistant Executive Engineer
(Seal & Signature)

District Officer
(Seal & Signature)