

SI.No	Item Name	Rate	Unit	Qty	Total
1	Flushing (Developing) Borewell (Code: GWDDR105)	5790.00	each	1.00	5790.00
2	Compressor pump 2 HP single phase (Code: GWDMR065)	25080.00	each	1.00	25080.00
3	Compressor pump fitting charge (Code: GWDDR055)	5222.95	each	1.00	5222.95
4	Providing and fixing G.I. pipes complete with G.I fittings including trenching and refilling etc. External work 25 mm dia nominal bore (18.12.3) (Code: GWDDR243)	524.12	meter	15.00	7861.84
5	20 mm dia HDPE pipe (DG) (8kg) (Code: GWDMR076)	15.00	meter	50.00	750.00
6	32 mm dia UPVC pipe (Code: GWDMR072)	270.00	meter	60.00	16200.00
7	Providing and fixing G.I. Union in G.I pipe including cutting and threading the pipe and making long screws etc. complete (New work): 32 mm nominal bore (18.46.4) (Code: GWDDR271)	513.49	each	1.00	513.49
8	GI Bend 32 mm (Code: GWDMR052)	132.00	each	1.00	132.00
9	14 mm thick nylon rope (Code: GWDMR069)	49.20	meter	65.00	3198.00
10	Supply and drawing FRLS PVC insulated & sheathed 650/1100 V grade 3 core copper conductor flat cable for submersible pump motor conforming to IS 694 part I 1990 as required including giving necessary connections of the following sizes. 4 sq mm (90.6.6.3) (Code: GWDDR117)	136.65	meter	20.00	2733.01
11	Well Protection Cover (Code: GWDDR001)	5489.10	each	1.00	5489.10

SI.No	Item Name	Rate	Unit	Qty	Total
12	Providing and fixing gun metal non-return valve of approved quality (screwed end): 40 mm nominal bore Horizontal (18.19.3.1) (Code: GWDDR260)	1022.06	each	1.00	1022.06
13	40 mm SS Adapter (Code: GWDMR080)	960.00	each	1.00	960.00
14	Metallic Pump House of size 1.2 x 0.9 x 2 m (Code: GWDDR006)	37557.00	each	1.00	37557.00
15	Installation of Single Phase Panel board where new electricity connection is required (Excluding Motor Starter) (Code: GWDDR363)	14281.08	each	1.00	14281.08
16	S & F Motor starters of the following ratings Submersible pump controllers with ammeter,DPMCB for single phase 2 HP submersible motor pumps (DOL) (90.14.28.13) (Code: GWDDR134)	1961.22	each	1.00	1961.22
17	Estimate For Fabricated Angle Iron Structure To Support 3000 Litres Capacity Water Tank At 4 m Height (Code: GWDDR003)	89559.00	each	1.00	89559.00
18	Providing and placing on terrace (at all floor levels) polyethylene water storage tank :ISI 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. (Code: 18.48)	12.15	Litre	3000.00	36444.74
19	PVC Tank connector 40 mm (Code: GWDMR035)	240.00	each	1.00	240.00
20	PVC Tank connector 50 mm (Code: GWDMR036)	288.00	each	1.00	288.00
21	PVC Ball valve 40 mm (Code: GWDMR042)	336.00	each	1.00	336.00
22	PVC Ball valve 50 mm (Code: GWDMR043)	456.00	each	1.00	456.00
23	Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 50 mm dia 10Kg/cm2 (50.18.9.6.1) (Code: GWDDR192)	319.82	meter	100.00	31982.10

Sl.No	Item Name	Rate	Unit	Qty	Total
24	Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching refilling & testing of joints complete as per direction of Engineer in Charge 40 mm dia 10Kgf/cm2 (50.18.9.5.1) (Code: GWDDR190)	311.80	meter	100.00	31180.10
25	Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.32 mm dia 10.Kgf/cm2 (50.18.9.4.1) (Code: GWDDR188)	272.51	meter	100.00	27251.05
26	Providing and fixing PVC pipes includes jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 25 mm dia 10KGF/cm2 (50.18.9.3.2) (Code: GWDDR187)	249.80	meter	100.00	24980.05
27	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil. and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m: All kinds of soil Pipes, cables etc, not exceeding 80 mm dia (Code: 2.10.1.1)	320.43	metre	250.00	80108.36
28	Hydrants with tap (for individual families of size 0.6 X 0.3 M platform) (Code: GWDDR062)	2160.31	each	10.00	21603.14
29	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) (Code: 15.2.1)	2516.93	cum	6.00	15101.55

SI.No	Item Name	Rate	Unit	Qty	Total
30	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4)1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) (Code: 4.1.4)	9062.65	cum	6.00	54375.89
Subtotal					542658.00
GST (18%)					97678.00
Unforeseen (max 2.5%)					16008.00
Grand Total Rounded to Next 1000					657000.00

Assistant Engineer
(Seal & Signature)

Assistant Executive Engineer
(Seal & Signature)

District Officer
(Seal & Signature)