

Sl.No	Item Name	Qty	Unit	Rate	Total
1	Flushing (Developing) Borewell (Code: GWDDR105)	1.0000	each	5790.00	5790.00
Pump & Accessories					
2	Compressor pump 2 HP single phase (Code: GWDMR065)	1.0000	each	27540.00	27540.00
3	Compressor pump fitting charge (Code: GWDDR055)	1.0000	each	3615.75	3615.75
4	Providing and fixing G.I. pipes complete with G.I fittings including trenching and refilling etc. External work 25 mm dia nominal bore (18.12.3) (Code: GWDDR243)	15.0000	meter	362.84	5442.60
5	20 mm dia HDPE pipe (DG) (8kg) (Code: GWDMR076)	50.0000	meter	15.00	750.00
6	32 mm dia UPVC pipe (Code: GWDMR072)	60.0000	meter	270.00	16200.00
7	Providing and fixing G.I. Union in G.I pipe including cutting and threading the pipe and making long screws etc. complete (New work): 32 mm nominal bore (18.46.4) (Code: GWDDR271)	1.0000	each	355.48	355.48
8	14 mm thick nylon rope (Code: GWDMR069)	65.0000	meter	49.20	3198.00
9	Supply and drawing FRLS PVC insulated & sheathed 650/1100 V grade 3 core copper conductor flat cable for submersible pump motor conforming to IS 694 part I 1990 as required including giving necessary connections of the following sizes. 4 sq mm (90.6.6.3) (Code: GWDDR117)	20.0000	meter	132.45	2649.00
10	GI Bend 40 mm (Code: GWDMR053)	1.0000	each	162.00	162.00

[illegible]

Sl.No	Item Name	Qty	Unit	Rate	Total
23	PVC Ball valve 50 mm (Code: GWDMR043)	1.0000	each	456.00	456.00
Pumping & Distribution Network					
24	Providing and fixing PVC pipes including jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 50 mm dia 10Kgf/cm ² (50.18.9.6.1) (Code: GWDDR192)	100.0000	meter	258.40	25840.00
25	Providing and fixing PVC pipes including jointing of pipes with one step PVC solvent cement, trenching refilling & testing of joints complete as per direction of Engineer in Charge 40 mm dia 10Kgf/cm ² (50.18.9.5.1) (Code: GWDDR190)	100.0000	meter	250.38	25038.00
26	Providing and fixing PVC pipes including jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 32 mm dia 10.Kgf/cm ² (50.18.9.4.1) (Code: GWDDR188)	100.0000	meter	215.37	21537.00
27	Providing and fixing PVC pipes includes jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 25 mm dia 10KGF/cm ² (50.18.9.3.2) (Code: GWDDR187)	100.0000	meter	192.66	19266.00
28	Hydrants with tap (for individual families of size 0.6 X 0.3 M platform) (Code: GWDDR062)	10.0000	each	1702.31	17023.10
Supplementary Works					

Sl.No	Item Name	Qty	Unit	Rate	Total
29	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil. and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m: All kinds of soil Pipes, cables etc, not exceeding 80 mm dia (Code: 2.10.1.1)	250.0000	metre	221.83	55457.50
30	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix) (Code: 15.2.1)	6.0000	cum	1742.42	10454.52
31	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4) 1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) (Code: 4.1.4)	6.0000	cum	6273.90	37643.40
32	KSEB Charges	-	-	-	1.00
Subtotal					412398.00
GST (18%)					74232.00
Unforeseen (max 2.5%)					12165.00
Grand Total Rounded to Next 1000					499000.00
Amount in Words: Four Lakh, Ninety-Nine Thousand Rupees Only					
<i>All Items should be as per ISI Standards</i>					

Assistant Engineer
(Seal & Signature)

Assistant Executive Engineer
(Seal & Signature)

District Officer
(Seal & Signature)