

asdasd

asdadd

Sl.No	Item Name	Qty	Unit	Rate	Total
1	110mm (4.5") Borewell Drilling (Code: GWDDR100)	100	metre	390.00	39000.00
2	Supplying, assembling, lowering and fixing in vertical position in Borewell, PVC 140 mm 6 Kg/cm2 well casing pipe of required dia, conforming to IS : 4985:2000, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer- in-Charge. (Code: GWDDR007)	20	metre	562.90	11258.00
3	Supplying, assembling, lowering and fixing in vertical position in Borewell, PVC 110 mm 6 Kg/cm2 well casing pipe of required dia, conforming to IS : 4985:2000, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer- in-Charge. (Code: GWDDR014)	80	metre	342.25	27380.00
4	PVC End cap 140 mm (DG) (Code: GWDMR003)	1	each	75.50	75.50
asdsd					
5	asdad	1.0	ssd	55.00	55.00

Sl.No	Item Name	Qty	Unit	Rate	Total
6	Cutting branches of trees overhanging above any structures of girth between 90cm to 120cm including stacking of serviceable materials and disposal of unserviceable material, cost of labour, hire charges of rope and pulley etc without making any damages to nearby structures etc complete. (Code: 50.2.33.7)	1	each	636.27	636.27
Subtotal					78405.00
GST (18%)					14113.00
Unforeseen					2482.00
Final Total (Rounded to 1,000)					95000.00
Amount in Words: Ninety-Five Thousand Rupees Only					
<i>All Items should be as per ISI Standards</i>					
adadda					

**Assistant Engineer
(Seal & Signature)**

**Assistant Executive Engineer
(Seal & Signature)**

**District Officer
(Seal & Signature)**